



Commercial Installation Projects

MEINCO WASTEWATER SYSTEMS



Commercial Installations

PINNACLE MOUNTAIN STATE PARK VISITOR CENTER

10,000 gallon septic tank, 5,000 gallon dose tank, 1000' of transport line, (4) disposal zones, 800' of line per zone, slave dose pump to each zone. Control panel to manage flows with telemetry. Installed 2023.

[Photos](#)

ACADEMICS PLUS / SCOTT SCHOOL

Lift station, duplex pumps, 8,000 gallon trash tank, 10,000 gallon anoxic tank, 10,000 gallon aeration tank with (12) double stack Biobarrier membrane, UV disinfection, direct discharge. Installed 2023.

[Photos](#)

HALE TRAILER

Two 1500 gallon STEP tanks, 900' of transport line, 400' of disposal zone. Installed 2023.

[Photos](#)

ARAUCO

2,000 gallon trash tank, duplex pumps to feed two HSFASST 1.5's, 2,000 gallon dose tank, duplex pumps, headworks box, 800' transport line, 10,000 square feet of drip dispersal. Installed 2022.

[Photos](#)

ECHO CANYON RESORT AND MARINA

Lift station, duplex pumps, 2500' transport line, 1,500 gallon trash tank, 1,250 gallon aeration tank, 1,500 gallon dose tank, 400' of line in disposal area.

Eight 1,000 gallon STEG tanks gravity fed to 3,000 gallon recirculation tank, two AX100 treatment pods, 1,500 gallon dose tank, headworks box, 600' transport line, 10,000 square feet of drip dispersal. Installed 2015.

Meinco Wastewater Systems
(501) 821-3837
P.O. Box 1001
Bryant, AR 72089



BEST FRIENDS ANIMAL HOSPITAL

Lift station, duplex pumps, 1,500 gallon trash tank, 2,000 gallon pre-aeration tank, 2,000 gallon aeration tank with (2) Biobarrier membranes, UV disinfection, direct discharge. Installed 2018.

NATURAL STATE MEDICINALS

1,500 gallon trash tank, duplex pumps, 10,000 gallon septic tank, 5,000 dose tank, duplex pumps, 7 zone headworks, 3,000' transport line, (7) disposal zones, 500' of line per zone, Control panel to manage flows. Installed 2022.

WACO BOATS

Two 1,500 gallon STEP tanks, 500' transport line, 1,500 gallon trash tank, (2) FAST 1.0's, 1,500 gallon settling tank, UV disinfection, sample/dose basin, direct discharge

ENTERGY UNION COUNTY

Lift station, duplex pumps, 1,000 septic tank, 500 gallon STEP tank, 1,500' transport line, 1,500 gallon trash tank, 1,500 gallon dose tank, 2,500' transport line, 400' of line disposal area.

ENTERGY HOT SPRING

Lift station, duplex pumps, 600' transport line, 5,000 gallon fiberglass holding tank with alarm.

ENTERGY REMMEL DAM

Lift station, duplex pumps, 3,000' transport line, manhole, public sewer.

BATES DISTRIBUTING

1,500 gallon trash tank, (1) FAST 1.5, UV disinfection, surface discharge

CHEROKEE LAKE RV PARK PHASE I

3,000 gallon septic tank, 1,500 gallon dose tank, duplex pumps, 600' of line in disposal area, traditional field lines.

CHEROKEE LAKE RV PARK PHASE II

3,000 gallon septic tank, 1,500 gallon dose tank, duplex pumps, 600' of line in disposal area, traditional field lines.



CHEROKEE LAKE RV PARK PHASE III

1,500 gallon septic tank, 1,500 gallon dose tank, duplex pumps, 300' of line in disposal area, traditional field lines.

CAMP KIA KIMA

10,000 gallon septic tank, 5,000 gallon dose tank, duplex pumps, (2) zones, 600' of field line in disposal area, traditional field lines.